



## Memorandum of SEPA Exemption

Project: South Terminal Stormwater System Maintenance and Improvements  
CIP No.: 1-8-001-06  
Port SEPA No.: 2017-07  
Location: Port of Everett, Marine Terminals  
3310 Terminal Avenue  
Everett, WA 98201

The Port of Everett has assumed lead agency status for review of the above-referenced project in compliance with SEPA (WAC 197-11). The Port has determined that the proposed project is categorically exempt from SEPA review under the provisions of:

- WAC 197-11-800 (3) for “The repair, remodeling, maintenance or minor alteration of existing private or public structures, facilities or equipment, including utilities ... involving no material expansions or changes in use beyond that previously existing...”

A copy of the project description and vicinity map are attached to this memorandum. Questions with regard to this memorandum should be direct to:

Laura M. Gurley, Planner  
Port of Everett  
PO Box 538  
Everett, WA 98206  
(425) 388-0720

Paul Brachvogel  
Paul Brachvogel, Chief of Legal Affairs  
Port SEPA Responsible Official

10/17/17  
Date Issued

Distribution:  
Project File  
Port Website

## **South Terminal Stormwater System Maintenance and Improvements Project Description for SEPA Exemption**

---

Port of Everett proposes to repair and improve a portion of the existing stormwater collection and treatment system at the South Terminal facility.

The proposed work includes replacing 17 lineal feet (LF) of existing 12-inch diameter buried conveyance/collection pipe, installation of a new Type II 48-inch diameter catch basin, installation of a modular wetland system vault (measuring approximately 5-feet high X 17-feet long X 9-feet wide) to improve stormwater treatment, and replacement of the existing 12-inch diameter outfall pipe with a 15-inch diameter outfall pipe at the same location and elevation. Approximately 96 cubic yards of material will be excavated and approximately 5 cy of fill (mostly bedding material) will be utilized. The collection area of the existing stormwater system will remain the same, so no change in volume of stormwater conveyed and discharged, nor location of outfall is proposed. This project will result in improved stormwater treatment prior to discharge.

The outfall replacement work will occur at approximately +11.6 feet elevation (MLLW). There is no new overwater coverage and no in-water work proposed as part of this work.

Actual construction will take approximately 30 to 60 days.

See attached exhibit for vicinity map.



Port of Everett

# PORT OF EVERETT

## South Terminal Stormwater System Maintenance and Improvements SEPA Exemption 2017-07 Project Vicinity

